

STEVE BLOIS, PRESIDENT
DIVISION 5

RAUL AVILA, SECRETARY
DIVISION 1

ANDY WATERS, DIRECTOR
DIVISION 3



ANDRES SANTAMARIA, VICE PRESIDENT
DIVISION 4

SCOTT H. QUADY, TREASURER
DIVISION 2

ANTHONY GOFF
GENERAL MANAGER

web site: www.calleguas.com

2100 OLSEN ROAD • THOUSAND OAKS, CALIFORNIA 91360-6800 805/526-9323 • FAX: 805/522-5730

April 18, 2023

Paul McClaren
Senior Planner
City of Camarillo
601 Carmen Drive
Camarillo, CA 93010

Subject: Five Year Capital Improvement Projects

Dear Mr. McClaren:

The following is provided in response to your e-mail dated March 31, 2023 requesting information on capital projects. Calleguas has the following projects planned in Camarillo in the next five years.

Project	Location and Description	Estimated Cost	Project Status
Somis Farmworker Housing SMP Discharge Station	Metering station for discharge of brine and recycled water from the farmworker housing development adjacent to the North Pleasant Valley Desalter into the Salinity Management Pipeline.	~\$300K	Design in progress
OSR Feeder and Santa Rosa Hydro Improvements	Improvements to address surge concerns, improve operability and reliability, and avoid failure of aging components. (One project element is located in Camarillo.)	~\$4M	Design in progress
Salinity Management Pipeline, Phase 3	Approximately 5 miles of 24" PVC pipe from the intersection of Upland and Lewis Rds. to Santa Rosa and Hill Canyon Rds.	~\$21M	CEQA in progress
Calleguas-Ventura Interconnection	Approximately 7 miles of 36" pipeline connecting the City of Ventura and Calleguas water systems, connecting to Calleguas' system near the intersection of Camino Tierra Santa and Via Zamora.	~\$21.5M	Design in progress

Please contact me at (805) 579-7156 or fbaez@calleguas.com if you have any questions or need additional information.

Sincerely,

A handwritten signature in blue ink, appearing to read "F Baez", is written over a horizontal line.

Fernando Baez, P.E.
Manager of Engineering